



Krishna Kanta Handiqui State Open University
Patgaon, Rani Gate, Guwahati-781017
Advertisement No: KKHSOU/Advt./2021/28
File No: KKHSOU/Construction/34/2010

Re- Tender

(Ref: KKHSOU/Advt./2021/25, dated 13-04-2021)

Krishna Kanta Handiqui State Open University, Guwahati invites sealed quotations from the Government registered Contractors for Supplying and Construction of ramp along with rail at the entrance gate and Repairing and Renovation of staff quarter. They may quote their best rate (inclusive of all taxes) in the specified format given below. The quotation superscribe with “Construction of Ramp and Repairing and Renovation of Staff Quarter” and addressed to “The Registrar, KKHSOU, University’s City Office, Resham Nagar, Khanapara, Guwahati-22 should reach the University office on or before **11/05/2021**. The date and place of the opening of tenders will be declared later on.

Date: 05.05.2021

Sd/-
Registrar

□

To
The Registrar
Krishna Kanta Handiqui State Open University, City Office, Resham Nagar, Khanapara, Guwahati-22

Sub: Construction of ramp along with rail at the entrance gate and repairing and renovation of staff quarter.

Sir,
With reference to above, I would like to offer my best rate for the following items –

A. CONSTRUCTION OF RAMP ALONG WITH RAIL AT THE ENTRANCE GATE AND THE 2ND RAIL AT STAIRCASE UPTO 2ND FLOOR OF THE MAIN BUILDING OF KKHSOU RANI, PATGAON.

Sl.No.	Description	Qty	Unit	Rate to be Offered (Inclusive all taxes)
1.	Demolishing mosaic floor of various thickness, both mosaic tiles and cast in situ type including CC base course and removal of debris as directed for all levels.	1.35	M2	
2.	Demolishing brickwork including stacking of serviceable materials and disposal of unserviceable materials as directed for all levels.	0.164	M3	
3.	Providing form work of ordinary timber planking so as to give a rough finish including centering, shuttering, strutting and propping etc. height of propping and centering below supporting floor to	0.96	M2	

	<p>celing not exceeding 4.0 M and removal of the same for in-situ reinforced concrete and plain concrete work in:</p> <p>4.Sides and soffits of Beams,beam haunshings, cantilever girders , lintels .</p> <p>(a) For depth not exceeding 1.00M</p> <p>(ii) Using 25mm thick plank</p>			
4.	<p>Providing and laying plain/ reinforced cement concrete works cement, coarse sand & 20mm downgraded stone aggregate including dewatering if necy. , and curing complete but excluding cost of form work and reinfor cement for reinforced cement concrete work(form work and reinforcement will be measured and paid separately)</p> <p>(II) Using Mixer Machine</p> <p>(C) In sub structure up to P.L.</p> <p>Foundation,footing,column.....P.L.</p> <p>b) M15 grade concrete or PROP. 1:2:4</p>	0.596	M3	
5.	<p>Providing and fixing Stainless Steel (Grade 304) railing made of Hollow tubes , channels, plates etc., including welding ,grinding, buffing, polishing and making curvature(whenever required) and fitting the same with necessarystainless steel nuts and bolts complete,i.e. fixing the railing with necessary accessories & stainless steel dash fasteners, stainless stel bolts etc. of required size on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer in charge(For payment only weight of stainless steel member is to be considered. No extra payment for fixing accessories such as nuts bolts ,fasteners etc. will be considered)</p>	225.82	KG	
6.	<p>Providing Antiskid Tiles of approved quality size,shape and thickness not less than 8mm on floor ,skirting over a cement mortar bed of 15mm thck in prop 1:3 (1 cement : 3 coarse sand) approved make fix with Fix-A- Tile(Choksey/ Ska/ Pedelite/ Rouf White cement complete at all level as specified and directed.</p> <p>(A) CERAMIC</p> <p>(I) Normal range(size 300mmx300mm and above</p> <p>(a) Orient made: Galaxy Brown, Galaxy creama, Galaxy Pink, Galaxy Green, Pulsar Beige</p>	2.88	M2	

B. REPAIRING AND RENOVATION OF STAFF QUARTER ALONG WITH NEW W.C BATH WITH SEPTIC TANK AND NECESSARY WATER SUPPLY ARRANGEMENT NEAR THE D.T.W. SITE AT KKHSOU RANI COMPLEX.

Sl.No.	Description	Qty	Unit	Rate to be Offered (Inclusive all taxes)
1.	<p>Earthwork in excavation for foundation trenches of wall, retaining walls, footing of column, steps, septic tank etc. including refilling the quantity as necy after completion of work, breaking clods in return filling ,dressing, watering and ramming etc, and removal of surplus earth with all lead and lifts as directed and specified in the following classification of soils including bailing out water where necy. As directed and specified.</p> <p>For extension of Ver along with kitchen & W.C.Bath</p> <p>(A) Up to a depth of 2.00m below existing ground level.</p> <p>b) In hard/dense soil</p>	11.46	M3	
2.	<p>Providing soling in foundation and under floor with stone/ best quality picked jhama brick, sand packed and laid to level and in panel after preparing the the sub grade as directed including all labour and materials and if necy. Dewatering ,complete.</p> <p>(a)Brick on flat soling.</p>	32.23	M2	
3.	<p>P.C.C Works</p> <p>Plain cement concrete works with coarse agg. Of sizes 13mm to 32mm in foundation bed for footing steps walls, brick works etc. as directed and specified including dewatering if necessary and curing complete (shuttering where necessary shall be measured and paid separately)</p> <p>(a) In prop. 1:3:6</p>	1.523	M3	
4.	<p>Supplying, fitting and fixing in position reinforcement bars conforming to relevant I.S. code for R.C.C Work/ R.B. walling including straightening ,cleaning, cutting and bending to proper shapes and length as per details supplying and binding with 20 G annealed black wire and placing in in position with proper blocks supports, chairs, spacers etc. complete .(No extra</p>	1.50	Qntl.	

11.	(a) Providing fitting and fixing 1 st class local wood battened , ledged and braced door window shutters including oxidized iron butt hinges (100mm x58mmx 1.90mm) 6ns.with necessary screws. (b)Using Gamari wood (i) 25mm thick	10.38	M2	
12.	Supplying, fitting ,fixing electrocoloured iron fitting of approved make resonbly smooth ,free from sharp edges and corners, flaws and other defects and with counter sunk holes for wood screws including necy. Screws etc. complete. a) Sliding door bolts(250mmx16mm 1x2 =2 nos. b) Tower bolts (iii) 200mmx10mm Door 1x4x3 =12 nos. Windows <u>1x5x2=10,,</u> 22 nos. c) Cast iron stove door handle ii) 100mm	2 22 11	Each Each Each	
13.	Providing wood work in frame of false ceiling partitions etc. sawn ,wrought ,framed hoisted and fixed in position with spikes, nails,M.S. flats, angle/ cleats withbolts and nuts complete including kiricide oiling two coats to unexposed surfaces of the timber(M.S. flats,anglecleats, boltand nuts required for flat,angle cleats wherever necessary shall be measured and paid separately) (B) With Gamari/Bonsum/Sundi	0.248	M3	
14.	Providing, fitting and fixing in position hardboard sheet ceiling with approved quality with necessary nails,wood screws including 1 st class local wood 50mm x12mm (hillock/bonsum/sundi) beading including painting two coat to timber beads complete as directed (ceiling joist to be measured and paid separately) © 6mm thick	26.59	M2	

15.	<p>Providing ,fitting and fixing M.S. grill of required pattern for windows/ clearstory windos/ opening with M.S. flats at rquird spacing in frame all round, squre or round M.S. bars with round headed bolts and nuts or screws.</p> <p>Plan grill</p> <p>(a) Fixed to wooden frame</p>	70.00	Kg	
16.	<p>Steel work welded in build up sections, framed work including cutting ,hoisting and fixing in positions and applying priming coat of red lead paint including drilling holes, supplying, fitting and fixing with bolts and nuts or welding , if necessary as directed.</p> <p>b) In trusses purlins op to 25m span and 15.0 m over all height.</p> <p>Roof truss M.S. Square hollow bar</p>	2.00	qntl	
17.	<p>Providing corrugated galvanized iron sheet roofing of TATA SHAKTEE/SAIL including fitting and fixing necessary galvanized J or L hooks, bolts and nuts 8mm dia withbitumen washer 25mm diax 3mm thick and 1.6 mm thick limpet washer complete excluding cost of roof trusses and purlin etc. to be measured and paid separately)</p> <p>(e) 0.63 mm thick</p>	27.95	M2	
18.	<p>15mm thick cement plaster in single coat on single or half brick wall for interior plastering up to 1st floor level including arises, internal rounded angles ,not exceeding 80mm girth and finished even and smooth including curing complete as directed..</p> <p>b)In prop. 1:4</p>	94.34	M2	
19.	<p>a) Applying one coat of cement primer of approved brand and manufacture on new wall surface after thoroughly brooming the surface free from mortar droppings and other foregn matter and including preparing the surface even and sand papered smooth.</p>	94.34	M2	

20.	b) Finishing wall with water proofing cement paint of approved brand and manufacture and of required shade on new wall surface (two coats) to give an even shade after thoroughly brooming the surfaces to remove all dirt and remains of loose powdered materials.	217.43	M2	
21.	Applying priming coat over new wood and wood based surfaces over 100mm in girth/width after and including preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter sand papering and knotting. (a) With ready mixed paint wood primer (pink)	64.55	M2	
22.	Painting two coats (excluding priming coat) on new wood and wood based surface with enamel paint of approved brand and manufacture (Asian paint/Berger paint/ ICI Paint/J& N paint/Nerolac) to give an even shade including cleaning the surfaces of all dirt,dust and other foreign matter sand papering and stopping. (i) Surface over 100mm in width or girth (b) High gloss (Asian paint/Berger paint/ ICI Paint/J& N paint/Nerolac)	64.55	M2	
23.	Providing and fixing clear sheet glass beded in putty and fixed with/without wooden biding including necy. Cutting and glass to be required sizes(payment of wooden bead shall be made separately) (2) Area of glass pane exceeding 0.15 m2 but not exceeding 0.52m2 (b) 4.00mm thick	1.68	M2	
24.	Supplying and placing ferrocement septic tanks of rectangular shape in to pit with manhole cover with cleaning arrangement over single brick flat soling and 75 mm 1:3:6 P.C.C. Baffle wall ,inlet and outlet etc provided at suitable poins complete as directed.	1	Each	

25.	<p>Providing fitting and fixing vitreous water closet squatting pan (Indian type W.C. Orissa pattern) with all fittings and fixtures complete including cutting and making good to the walls and floors wherever required.(Flushing cistern to be paid separately)</p> <p>2. Indian type Orissa pattern of size 500mm a) White i) Parryware make</p>	1	Each	
26.	<p>Supplying ,fitting and fixing PVC flushing cistern with all internal CI brackets including fitting and fixing standard size cp flush pipe, union clamp etc. complete as directed and specified</p> <p>l) Parryware make a) White</p>	1	Each	
27.	<p>Supplying , fitting and fixing PVC pipes 6 Kg/cm²(Supreme/ Prince) or other ISI approved including jointing,fitting and fixing with clamps etc. as necessary complete at all levels including below G.L. as directed and specified.</p> <p>a) In exposed surface or in trenches. ii)110mm dia iii) 75mm dia</p>	8.00 2.00	M M	
28.	<p>Supplying fitting and fixing 87,5 degree PVC bend with door of (Supreme/Prince) or other ISI approved including joining, fitting and fixing etc.as necy. Complete at all levels including below G.L. as directed and specified.</p> <p>b) In exposed surface or in trenches. (ii) 110mm dia.</p>	1	Each	
29.	<p>Supplying fitting and fixing PVC single Tee with door of (Supreme/Prince) or other ISI approved including joining, fitting and fixing etc.as necy. Complete at all levels including below G.L. as directed and specified.</p> <p>c) In exposed surface or in trenches. (iii) 110mm dia.</p>	1	Each	

30.	Supplying fitting and fixing PVC reducer of (Supreme/Prince) or other ISI approved including joining, fitting and fixing etc.as necy. Complete at all levels including below G.L. as directed and specified. d) In exposed surface or in trenches. (iv) 110mm x75mm	1	Each	
31.	Supplying fitting and fixing Ajoy Flowguard CPVC (Chlorinated Polyvinyl Chloride) pipes having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fitting including clamps at 1.00 m spacing including jointing of pipes and fitting with one step CPVC solvent cement and testing of joints complete at all levels as directed and specified. e) In exposed surface or in trenches. (i) 15mm OD	35.00	M	
32	Supplying fitting and fixing polymer bib cock(15mm) of polymer prayag make directed and specified (G.I. & C.P. pipes will be measured and paid separately) Standard	3	Each	

Date:

Signature:

Name of the Contractor:

Address:

Contact No:

E-mail:

Documents to be submitted along with the quotation:

1. Copy of firm registration certificate/license of manufacturer/dealership certificate.
2. GST registration certificate
3. Income tax return document.
4. 2.5% of the quoted amount is required to be deposited as EMO along with tender document in the form of Demand Draft addressed to The Registrar, KKHSOU.
5. Rs. 1,000/-(non-refundable) in the form of Demand Draft addressed to The Registrar KKHSOU is required to be deposited as tender fee.